



Passivent

North Frith Oasts, Ashes Lane, Hadlow,
Kent TN11 9QU

Telephone **01732 850 770**

Fax **01732 850 949**

Email **projects@passivent.com**

Website **www.passivent.com**

Airscoop Terminals

Provide ventilation by means of Passivent Basic/DAD/RAD* Airscoop roof-mounted ventilation terminals in Modern/Traditional/Circular* style with automatic damper control.

Terminals to have been appraised under BS EN ISO 9001. Terminals of high-impact ABS with all exposed surfaces treated with UV-stable polymeric resin, sub base of external grade plywood. Weather performance tested to BS EN 13030 'Performance testing of louvres subjected to simulated rain': patented double-bank louvres Class A 100% at 0.00m/s, Class A 100% at 0.50m/s.

Thermal insulation U-value 1.6W/m²K when basic dampers are closed, 24V modulating actuator for internal dampers controlled by iC8000. Resistant to continuous wind loads at 51m/s via independent test, 4mm insect screen. Terminal widthmm, lengthmm, roof pitch Colour and texture to RAL / BS colour or to match roof covering*. Installed by an approved installer.*

Ventilators designed and manufactured under BS EN ISO 9001, and supplied by Passivent, North Frith Oasts, Ashes Lane, Hadlow, Kent TN11 9QU Tel: 01732 850770, Fax: 01732 850949, Email: projects@passivent.com (and installed by an approved installer).

*Delete as applicable.

